



Office

Conventional Steel Framing Study



**STEEL SOLUTIONS
CENTER**

www.aisc.org/askaisc
866.ASK.AISC | solutions@aisc.org


Project Information

- Minneapolis, Minn.
- Four-story office building
- Conventional composite steel beam gravity framing
- Steel ordinary concentrically braced frames and moment frames
- Typical floor-to-floor height: 14'-0"


Architectural Floor Plans




First Floor Plan




Second and Third Floor Plans



Concentrically Braced Frame



Moment Frame



Fourth Floor Plan


Cover rendering courtesy of Ryan A+E.

.....

This document has been prepared in accordance with information made available to the American Institute of Steel Construction at the time of its preparation. While it is believed to be accurate, it has not been prepared for conventional use as an engineering or construction document and should not be used or relied upon for any specific application without competent professional examination and verification of its accuracy, suitability and applicability by a licensed engineer, architect or other professional. AISC disclaims any liability arising from information provided by others or from the unauthorized use of the information contained in this document.

Typical Structural Framing Plan

See pages 5 through 8 for detailed framing plans and frame elevations.



Steel Quantity Totals

See page 4 for detailed steel quantity information.

Total Building Area = 192,730 sq. ft				
Total Steel Tonnage	Total Pounds Per sq. ft	Total Pieces	Total Studs	Total Cambered Beams
728	7.55	939	10,722	354

Steel Benefits



Long-span beams with open, column-free spaces attract potential tenants, providing flexibility for office layout.



Steel framing can more easily be adapted for future changes in loading conditions, vertical expansion, and changes in occupancy than other framing systems.



Steel framing will reduce overall project costs, including lower foundation costs due to steel's higher strength-to-weight ratio, general condition savings due to faster construction schedules, and increased revenue from earlier occupancy thanks to faster construction.



Structural steel's recycled content and recycling rate exceed those of any other construction material, with steel produced within the United States containing approximately 93% recycled steel scrap and 98% of all structural steel recycled back into new steel products, at the end of a building's life.

Schedule and Pricing

Contact the Steel Solutions Center for assistance with locating an AISC member fabricator in your area for pricing and schedule information. You may also search our website for further information on member fabricators in your region. AISC member fabricators are an excellent source of pricing and schedule information. E-mail solutions@aisc.org or call 866.ASK.AISC to find an AISC member fabricator in your area.

Loading Summary

Criteria are based on the 2012 *International Building Code (IBC)* and a project location of Minneapolis, Minn.

Gravity Loading		Seismic Loading	
Live Loads		Seismic Design Category	A
Office	65 psf (including 15 psf partition loading)	Seismic Importance Factor	1.00
Roof Deck	100 psf	Spectral Response Acceleration, Short Period, S_s	0.048 g
Roof Snow	50 psf	Spectral Response Acceleration, One Second Period, S_1	0.027 g
Dead Loads		Site Class	D
Typical Floor	46 psf (3 in. metal deck with 3¼ in. LW Concrete)	Building Period Coefficient, C_T	0.02
Roof	4 psf (3 in. metal deck)	Response Modification Factor, R	3.00
Superimposed Dead Loads		System Overstrength Factor, Ω_0	3.00
Office	10 psf (CMEP, etc.)	Deflection Amplification Factor, C_d	3.00
Occupied Roof	45 psf (CMEP, pavers, roofing, etc.)	Allowable Story Drift Coefficient	0.02
Unoccupied Roof	20 psf (CMEP, roofing, etc.)	Lateral Force Resisting System	
Cladding		Steel Systems Not Specifically Detailed For Seismic Resistance	
Brick Façade	770 plf	Risk Category	II
Wind Loading			
Basic Wind Speed	115 mph		
Exposure Category	C		
Drift Limit	H/500		

Steel Quantity Takeoff

Suspended Steel Floor Areas		Total Area	192,730 ft ²	
		Typical Floor	155,340 ft ²	
		Roof	37,390 ft ²	
Estimated Steel Quantities				
Gravity Columns	W14s	63 tons	0.65 psf	109 pieces
Gravity Beams	Wide Flange	535 tons	5.55 psf	695 pieces
		10,722 studs		
		354 Beams cambered between 0.75 and 2.00 inches		
Lateral Frames	Beams	38 tons	0.39 psf	43 pieces
	Columns	44 tons	0.46 psf	66 pieces
	Braces (HSS)	13 tons	0.13 psf	26 pieces
Steel not indicated in sketches (5%)		35 tons	0.36 psf	
		728 tons	7.55 psf	939 pieces

Notes

1. The quantities are based on centerline dimensions.
2. Steel not indicated in sketches accounts for framing not included in the estimate such as framing for openings or various members eliminated for simplification. It does not include connection material, slab edge material or façade attachments.


Material Specification


1. Wide flange shapes are ASTM A992
2. Rectangular HSS sections are ASTM A500 Gr. C.

Fourth Floor Framing Plan

Notes:

- Each member is marked with the estimated member size for wide-flange (W) beam and the designation for camber. If present, the designation "C" indicates an assumed camber from 3/4 in. to 2 in. The estimated number of studs for each member is not indicated; a total estimated number of studs is provided in the quantities.
- Boxes** indicate lateral frames. The wide-flange beams are moment-connected to the columns in the moment frames and pin-connected to columns in the braced frames. NO special base plate detail is assumed for the columns.
- \swarrow indicates the direction of the estimated floor slab, which consists of 3 in. composite metal deck with 3 1/4 in. lightweight concrete topping.
- See the Column and Frame Layout Plans and the Column Schedule for gravity column sizes.
- All beams are W12x14, unless noted otherwise.






Roof Framing Plan

Notes:

- Each member is marked with the estimated member size for wide-flange (W) beam and the designation for camber. If present, the designation "C" indicates an assumed camber from $\frac{3}{4}$ in. to 2 in. The estimated number of studs for each member is not indicated; a total estimated number of studs is provided in the quantities.
- Boxes indicate lateral frames. The wide-flange beams are moment-connected to the columns in the moment frames and pin-connected to columns in the braced frames. NO special base plate detail is assumed for the columns.
- \swarrow indicates the direction of the estimated roof slab, which consists of 3 in. metal deck.
- See the Column and Frame Layout Plans and the Column Schedule for gravity column sizes.
- All beams are W12x14, unless noted otherwise.

Column Layout Plan





Column Schedule

Roof EL = 69'-6"		W14x43										
4th Floor EL = 55'-6"			W14x43									
3rd Floor EL = 41'-6"		W14x61	W14x53	W14x61	W14x48	W14x43	W14x43	W14x48	W14x43	W14x43	W14x43	W14x43
2nd Floor EL = 27'-6"		W14x74	W14x68	W14x82	W14x61	W14x43	W14x53	W14x61	W14x61	W14x48	W14x43	W14x43
1st Floor EL = 12'-0"												
Basement EL = 0'-0"												
COLUMN MARK	C1	C2	C3	C4	C5	C6	C7	C8	C9	C10	C11	

Frame Elevations

Notes:


- All braces are HSS8x8x1/2, unless noted otherwise.




Frame Elevations

Notes:


1. All braces are HSS8x8x1/2, unless noted otherwise.




MOMENT FRAME 3



MOMENT FRAME 4



BRACED FRAME 5



MOMENT FRAME 6

IDEAS² Award-Winning Office Projects

National Award
.....

**Samsung Americas Headquarters
(Device Solutions)**

San Jose, Calif.



Tim Griffith Photographer, San Francisco

Presidential Award
of Excellence in
Engineering
.....

**Four World
Trade Center**

New York



Joe Woolhead Photography



Smarter. Stronger. Steel.

.....
American Institute of Steel Construction
312.670.2400 | www.aisc.org