



**AISC**  
**Night School**

Thank you for joining our live webinar today.  
We will begin shortly. Please standby.

Thank you.  
Need Help?  
Call ReadyTalk Support: 800.843.9166

**Steel Construction** | From the Mill to  
Topping Out



**Smarter.  
Stronger.  
Steel.**



Today's audio will be broadcast through the internet.

Alternatively, to hear the audio through the phone, dial 866-519-2796. Passcode: 387037



Today's live webinar will begin shortly.  
Please standby.

As a reminder, all lines have been muted. Please type any questions or comments through the Chat feature on the left portion of your screen.

Today's audio will be broadcast through the internet. Alternatively, to hear the audio through the phone, dial 866-519-2796. Passcode: 387037



*AISC is a Registered Provider with The American Institute of Architects Continuing Education Systems (AIA/CES). Credit(s) earned on completion of this program will be reported to AIA/CES for AIA members. Certificates of Completion for both AIA members and non-AIA members are available upon request.*

*This program is registered with AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.*

*Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.*





### Copyright Materials

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of AISC is prohibited.

© The American Institute of Steel Construction 2018



### Session Description

#### **18.5 Steel Erection: It doesn't get built without the erector November 19, 2018**

Structural steel erection consists of assembling the building's frame on site safely and economically. This session will address how steel erection gets done, from securing the work to executing it. Topics include:

- Erectors' contractual relationships
- Estimating
- AISC Code of Standard Practice
- Erection schematic
- Selling an erection project
- Contracts
- Prefabrication coordination
- Erection pre-mobilization planning
- Prosecuting the work



### Learning Objectives

- List items that a steel erector must extract from a project's construction documents for supporting an accurate estimate.
- Identify good and bad steel details that affect a steel erector's ability to safely and efficiently perform work.
- List items addressed in a site safety plan.
- List steel erection challenges and solutions highlighted through real project examples.

### **Night School 18: Steel Construction Session 5: It doesn't get built without the Erector**

**November 19, 2018**



Phil Torchio  
President – CEO, Retired  
Williams Enterprises of Georgia  
parent of Williams Erection Company  
Atlanta Steel Erectors  
Smyrna, GA



**Smarter.  
Stronger.  
Steel.**



## Night School 18

- 18.1 **Introduction** to the Steel Construction Process Oct. 15
- 18.2 The **Manufacturing** of Structural Steel Shapes Oct. 22
- 18.3 A Virtual, Detailed Tour of the **Steel Fabrication** Process Oct. 29
- 18.4 **Connection Design** as the Fabricator's Representative Nov. 5
- **18.5 It Doesn't Get Built Without the Erector** Nov. 19
- 18.6 **Erection Engineering** – Stability During Construction Nov. 26
- 18.7 **Field Fixes** and Solutions Dec. 3
- 18.8 **Quality Control** and Quality Assurance Dec. 10



### The Plan for Today:

#### Part One:

- Who we are and how we get work to perform
- Estimating the job
- AISC Code of Standard Practice
- Construction Contracts for Erectors
- Erection scheme committed to paper or model
- Selling an Erection Project

#### Part Two:

- We have a contract, now what?
- Erector Pre mobilization planning
- Site specific Erection plan
- Engineered Stability Plan
- Doing the Work

#### Part Three:

- Questions



## Our Community

- Per Manta there are 1,197 Structural Fabricators in the USA, AISC says 1,700
- Per Manta there are 12,733 or 11,261 or 10,086 Steel Erectors



- Changes per the day you search the internet. But there is an order of magnitude more erectors than fabricators



12



## Part One

### Where do the jobs come from?

- 95% of requests for quotation come from Fabricators that we have performed work for in the past
- Pre Qualification requirements of General Contractor / Construction Manager (Owner's Designated Representative for Construction (ODRD))
  - AISC Erector Qualification
  - Bonding Capacity
  - Safety Record
- Drawings, Models and Specifications Furnished by Fabricator
  - In the olden days hard copies now all electronic
- Sample Contract Documents
- Site Visit



13

## Estimate - Drawing Review

- Architectural Drawings for Elevations
- Civil drawings site layout
- Structural Drawings S001 General Structural Notes
- S100 –S500 Structural Drawings
- Specifications 5000 series:

From the Job Specifications - AISC Code of Standard Practice

#### 2.4 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate according to AISC's "Code of Standard Practice for Steel Buildings and Bridges" and AISC's "Specification for Structural Steel Buildings--Allowable Stress Design and Plastic Design."

#### ERECTION

- B. Set structural steel accurately in locations and to elevations indicated and according to AISC's "Code of Standard Practice for Steel Buildings and Bridges" and "Specification for Structural Steel Buildings--Allowable Stress Design and Plastic Design."



14

## Estimate information

### From the drawings:

- Column counts (may vary if too heavy for crane(s))
- Beam/Girder count
- Truss and or joist count (Truss weights for crane)
- Stud count
- Bracing count, Vertical X or K
- Bracing horizontal
- Decking square footage
- Deck edge angle, bent plate, closure and support angle (attention to attachment)
- Bracing for edge bent plate etc.
- Roof frames - penetrations
- Moment connections
  - Calculate weld weight
- Welded column splices
  - Calculate weld weight
- Detail cost drivers special connections or conditions.



15

## Estimate information

### From the Fabricators:

- Bolt count and Bolt sizes
- Tonnage
- Stairs part of the package?
- Fabricator or Erector to furnish the Studs?
- Fabricator to drill holes for safety cable?
- Fabricator furnish safety cable posts?
- Column lifting holes?
- Special field weld preparations
- Shop assembly of components
- Shoring
- Bond



16



## Estimate information

### From the GC - ODRC:

- Job access
- Traffic control for material delivery
- Lay down area
- Gravel and dewatering
- Furnish cranes? What limitations for Erector
- Power 440 three phase?
- Special Safety requirements
- Site personnel requirements
- GC's on site management team
- CCIP OCIP Insurance (deductibles)



17

## AISC Code of Standard Practice

### 2016 Code of Standard Practice

#### Preface:

As in any industry, trade practices have developed among those that are involved in the design, purchase, fabrication and erection of structural steel. **This Code provides a useful framework for a common understanding of the acceptable standards when contracting for structural steel.** As such, it is useful for owners, architects, engineers, general contractors, construction managers, fabricators, steel detailers, erectors and others associated with construction in structural steel. **Unless specific provisions to the contrary** are contained in the contract documents, the existing trade practices contained herein are considered to be **the standard custom and usage of the industry** and are thereby incorporated into the relationships between the parties to a contract.



18


## AISC Code of Standard Practice

<b>SECTION 7. ERECTION</b> .....	39
7.1. Method of Erection .....	39
7.2. Job-Site Conditions .....	39
7.3. Foundations, Piers and Abutments .....	39
7.4. Lines and Benchmarks .....	39
7.5. Installation of Anchor Rods, Foundation Bolts, and Other Embedded Items .....	40
7.6. Installation of Bearing Devices .....	41
7.7. Grouting .....	41
7.8. Field Connection Material .....	42
7.9. Loose Material .....	43
7.10. Temporary Support of Structural Steel Frames .....	ODRD
7.11. Safety Protection .....	46
7.12. Structural Steel Frame Tolerances .....	46
7.13. Erection Tolerances .....	47
7.14. Correction of Errors .....	57
7.15. Cuts, Alterations and Holes for Other Trades .....	57
7.16. Handling and Storage .....	58
7.17. Field Painting .....	58
7.18. Final Cleaning Up .....	58

**Erector**  
**Owner's Designated Representative for Design**  
**General Contractor**  
**Fabricator**



19



Under the flange line through the base working point for an individual column in the foundation the flange line continues to the center line of the column. The established column line, foundations and anchor rods beyond the Erector's control.



20








**TABLE 10.1  
AESS Category Matrix**

Category	AESS C		AESS 4		AESS 3		AESS 2		AESS 1		SSS	
	Custom Elements	Characteristics	Showcase Elements	Feature Elements in close view	Feature Elements in slow view	Basic Elements	Standard Structural Steel					
1.1		Surface preparation to SSPC-SP 6	*	*	*	*	*	*	*	*	*	*
1.2		Sharp edges ground smooth	*	*	*	*	*	*	*	*	*	*
1.3		Continuous weld appearance	*	*	*	*	*	*	*	*	*	*
1.4		Standard structural bolts	*	*	*	*	*	*	*	*	*	*
1.5		Weld spatters removed	*	*	*	*	*	*	*	*	*	*
2.1		Visual samples	Required	*	*	optional	*	*	*	*	*	*
2.2		One-half standard fabrication tolerances	*	*	*	*	*	*	*	*	*	*
2.3		Fabrication marks not apparent	*	*	*	*	*	*	*	*	*	*
2.4		Welds uniform and smooth	*	*	*	*	*	*	*	*	*	*
3.1		Mill marks removed	*	*	*	*	*	*	*	*	*	*
3.2		Butt and plug welds ground smooth and filled	*	*	*	*	*	*	*	*	*	*
3.3		HSS weld seam oriented for reduced visibility	*	*	*	*	*	*	*	*	*	*
3.4		Cross sectional abutting surface aligned	*	*	*	*	*	*	*	*	*	*
3.5		Joint gap tolerances minimized	*	*	*	*	*	*	*	*	*	*
3.6		All welded connections	optional	optional	optional	optional	optional	optional	optional	optional	optional	optional
4.1		HSS seam not apparent	*	*	*	*	*	*	*	*	*	*
4.2		Welds contoured and blended	*	*	*	*	*	*	*	*	*	*
4.3		Surfaces filed and sanded	*	*	*	*	*	*	*	*	*	*
4.4		Weld show-through minimized	*	*	*	*	*	*	*	*	*	*
C.1												
C.2												
C.3												
C.4												

**AESS 1:** Basic elements.  
**AESS 2:** Feature elements viewed at a distance greater than 20 ft (6 m).  
**AESS 3:** Feature elements viewed at a distance less than 20 ft (6 m).  
**AESS 4:** Showcase elements with special surface and edge treatment beyond fabrication.  
**AESS C:** Custom elements with characteristics described in the *contract documents*.





S001  
General Structural Notes

25

S001 General Structural Notes

**Seismic Job**  
↓

SHAPE	MATERIAL
WIDE FLANGES & WTS	ASTM A992, GRADE 50
MISCELLANEOUS PLATES	ASTM A572, GRADE 50
CONTINUITY PLATES	ASTM A572, GRADE 50
ANGLES & CHANNELS	ASTM A36
RECTANGULAR HSS (TUBES)	ASTM A500, GRADE B
ROUND HSS	ASTM A500, GRADE B
BOLTS	ASTM A325 N, UON
ANCHOR RODS	ASTM F1554, Fy=36ksi, UON
THREADED RODS	ASTM A36
STEEL JOIST	PER STEEL JOIST INSTITUTE'S SPECIFICATIONS
WELDING ELECTRODES	E70, SEE SPECIFICATIONS FOR CVN REQUIREMENTS
WELDED STUDS	ASTM A108 HEADED STUDS: TYPE H4L OR S3L BY NELSON OR EQUAL.

Notes trigger closer examination and cost drivers

SS-2 STRUCTURAL STEEL MEMBERS AND CONNECTIONS DENOTED "SLRS" SHALL SATISFY REQUIREMENTS FOR THE SEISMIC LOAD RESISTING SYSTEM IN SPECIFICATION SECTION 05 12 10.

SS-3 WHERE NO CAMBER IS INDICATED, FABRICATE BEAMS SO THAT ANY NATURAL CAMBER IS UPWARD AFTER ERECTION

SS-4 SPLICES SHALL BE ALLOWED ONLY AT LOCATIONS SPECIFICALLY INDICATED ON THE STRUCTURAL DRAWINGS UNLESS APPROVED OTHERWISE BY THE SER IN WRITING.

SS-5 FOR STEEL MEMBERS AND EMBEDMENTS EXPOSED TO WEATHER, PROVIDE HOTDIPPED GALVANIZED FINISH.

SS-6 PROVIDE HOLES IN ALL STEEL AS REQUIRED TO PREVENT ANY ACCUMULATION OF WATER. ALL PENETRATIONS THROUGH MAIN MEMBERS SHALL NOT EXCEED 1 1/8" DIA AND SHALL BE GROUND SMOOTH. THESE DRAINS MUST BE KEPT CLEAN

26

Engineered Erection Stability Plan

SS-8 FIELD MODIFICATION OF STRUCTURAL STEEL IS PROHIBITED WITHOUT PRIOR APPROVAL OF THE ARCHITECT AND STRUCTURAL ENGINEER.

SS-9 THE CONTRACTOR SHALL SUBMIT A STEEL ERECTION PROCEDURE, PREPARED UNDER THE SUPERVISION OF A STRUCTURAL ENGINEER LICENSED IN THE STATE OF THE LOCATION OF THE PROJECT (THE CONTRACTOR'S ENGINEER) FOR REVIEW BY THE STRUCTURAL ENGINEER OF RECORD. THIS PROCEDURE MUST INCLUDE THE PROPOSED SURVEY REQUIRED BY THE STEEL SPECIFICATIONS.

SS-10 HOT ROLL SHAPES WITH FLANGE THICKNESS EXCEED 2 INCHES OR BUILT UP HEAVY SHAPES WITH PLATES EXCEED 2 INCHES IN THICKNESS USING COMPLETE JOINT PENETRATION GROOVE WELD THAT FUSE THROUGH THE THICKNESS OF THE FLANGE OR WEB OF JOINING COMPLETE JOINT PENETRATION WELD SPLICES SHALL HAVE A MINIMUM CHARPY V-NOTCH IMPACT TESTING VALUES OF 0 20 FT-LB AT A MAXIMUM TEMPERATURE OF +70 DEG. F. THE MAXIMUM TEST SHALL BE CONDUCTED IN ACCORDANCE WITH ASTM A673 FREQUENCY P. THE ABOVE REQUIREMENTS DO NOT APPLY IF THE SPLICES AND CONNECTIONS ARE MADE BY BOLTING.


SS-11 WELD ELECTRODES FOR THE HEAVY SHAPES NOTED IN SS-10 THAT REQUIRE CVN TESTING SHALL HAVE A CVN OF 20 FT-LB AT -20 DEG. F AND 40 FT-LB AT +70 DEG. F EXCEPT FOR STRUCTURE THAT IS NOT ENCLOSED AND MAINTAINED AT A TEMPERATURE OF +50 DEG. F OR HIGHER. THE TEST TEMPERATURE SHALL BE 0 EQUAL TO THE LOWEST ANTICIPATED SERVICE TEMPERATURE (LAST) PLUS 20 DEG. F. LAST SHALL BE -7 DEG. F.

SS-12 STEEL REINFORCEMENT TO EXISTING BEAMS AND COLUMNS SHALL BE WELDED BY QUALIFIED WELDERS USING TECHNIQUES AND SEQUENCES THAT MINIMIZE POST-WELD DISTORTION OF THE MEMBER. WELDING PROCEDURE SPECIFICATIONS AND WELDING SEQUENCES SHALL BE SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW.

SS-13 WHERE NEW STEEL BEAM FRAMING TIES INTO EXISTING STRUCTURE, FIELD APPLIED CONNECTION IS REQUIRED. CONNECTIONS SHALL BE DESIGNED BY CONTRACTOR'S STEEL CONNECTION DESIGN ENGINEER UON. CONTRACTOR RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF FIRE-PROOFING IF PRESENT AT CONNECTION.





Impact Requirements WPS and Welder





27




S100  
Level 2  
Framing Plan

28






Provide bolted field connections to assist location and plumbing  
Then field weld to structure.




37



38








39



40







## Estimate Erection Plan

We know:

- Material Quantities for Erection
- Site conditions for access, shake out, potential use of mobile crane
- Furnished Tower Crane capacity at each pick point
- Piece weight of each crane pick of concern
- Know (or suspect) the need for engineered stability plan
- Desired schedule from GC/Owner
- Contract issues that might drive cost
- Column lengths for Tower crane picks
- Use of large mobile crane at the lower level to avoid cuts
  - Cost of Field welded splice CJP
  - Time required for splice and impact to schedule
  - Do splices need to be complete prior to setting the next tier?
- Shoring and stability requirements
  - Preliminary contact with erection engineer for cost and ideas
- Fabricator's shipping schedule
- Sequences for the job

47

## Estimate Erection Plan cont.

We commit to the plan:

- Critical path Critical activity (often field welding or bolting)
- Staffing for this critical activity
- Equipment for this activity
- Second shift considerations or Overtime
- GC pour schedule drives clean up crew sizes
- Preliminary site specific safety plan
- Office management and field Project Engineer and Ironworker supervision

48

## Williams Erection Company

**Risk & Safety Program**

Site Specific Safety & Erection Plan  
Ally Charlotte Center  
601 South Tryon Street  
Charlotte, North Carolina




49

Table of Contents - I	
Table of Contents - I	2
Executive Summary	7
Executive Summary	8
Scope of Work	9
Site Specific JSSP	10
Site Safety Management	14
Site Safety Management Process	15
Weekly Toolbox Safety Meetings & STA's	16
Site Safety Inspections	17
Job Safety Analysis - JSA's	18
Gang Box Use	19
Training / Project Orientation	20
Williams Erection Company Substance Abuse Policy	21
Competent Persons	22
Material Delivery, Staging & Storage - As Applicable	23
Controlling Contractor - Authorization to Begin Steel Erection	24
Coordination With Other Trades/Construction Activities	25
Hoisting & Major Equipment Safety	26
Site Preparation	27
Steel Erection Procedure: Pre-Shift Inspections & Steel Erection	28
Steel Erection Procedure: Pre-Shift Inspections & Steel Erection	29
Steel Erection Procedure: Pre-Shift Inspections & Steel Erection	30
Steel Erection Procedure: Steel Erection Plan	31



50



The Not So Good  
Old Days



51

### WEC/ASE Job Safety Analysis & Training

#### Fall Protection Anchorage

Tasks Performed	Hazards / Fall Injury Potential
<p>We perform many tasks in steel erection that involve fall protection and the requirement to be off to a proper anchorage. These include:</p> <ul style="list-style-type: none"> <li>➢ Steel Erection</li> <li>➢ Welding</li> <li>➢ Use of Scaffolds</li> <li>➢ Climbing Vertical Ladders</li> <li>➢ Aerial Lift Operation</li> </ul>	<p>Erection Activities Exposure You to Hazards &amp; Injuries such as:</p> <ul style="list-style-type: none"> <li>➢ Fall from Erection</li> <li>➢ Fall from Scaffold</li> <li>➢ Fall from Ladders</li> </ul> <p>Resulting in:</p> <ul style="list-style-type: none"> <li>➢ Broken Bones</li> <li>➢ Severe Injury</li> <li>➢ Death</li> </ul>






#### Keys to Controlling the Hazards

- Only tie off to a proper anchorage capable of withstanding 5000 lbs of force/worker
- Tie off high - above your head if possible to limit fall distance.
- If using a choker, Use only a 5/16" choker for tie off. Use the shortest choker possible to wrap the structural member. Use the choker in back.
- If using a retractable, affix the retractable to a proper anchorage with the manufacturer supplied carabiner.
- If tying off to a retractable, tie off the retractable hook directly to the harness "D" ring or to a proper "D" ring extension. Never connect a retractable to a shock absorbing lanyard
- WEC/ASE engineered fall protection systems such as skinner lines, rat lines, horizontal life lines must be installed properly under the direction of a competent person and inspected on a daily basis. Always on both sides. Never inside a dead D-bolt.
- If using a rope grab, use rope in good condition and keep the rope grab above your head.
- If using a beamer, connect and adjust the beamer correctly.
- In an aerial lift - tie off only to the marked anchorage

Protect Yourself & Save Your Life!



52



## Gases, vapors, fumes, dusts, mists

- Engineering controls must be used first where feasible.
- When not feasible, PPE must be provided.
- PPE is always the last choice for protection.

55

		ATLANTA STEEL ERECTORS & WILLIAMS ERECTION COMPANY Safety Management System:		Doc No: SILICAEXPNT
		Initial Issue Date: 2-8-17	Revision Date: Initial Version	
<b>SILICA EXPOSURE CONTROL</b>		Preparation: Safety Mgr	Authority: President	Issuing Dept: Safety
		Revision No: 0	Next Review Date: 2-8-19	Page: Page 1 of 15

**Purpose**

The purpose of the silica exposure control plan (ECP) is to set out our approach to protecting workers from harmful exposure to respirable crystalline silica.

A combination of control measures will be required to achieve this objective. We commit to being diligent in our efforts to select the most effective control technologies available, and to ensure that the best practices, as described in this Exposure Control Plan (ECP), are followed at our worksites.

The work procedures we establish will protect not only our workers but all workers on our worksites. ASE has selected the use of Table 1 for compliance with exposure control program rather than IH sampling method. ASE utilizes DuWalt equipment that has been certified compliant with Table 1 requirements.

**Key Responsibilities**

Due to the significant risk posed by respirable crystalline silica, it is critical that all personnel involved in operations that could potentially create silica dust take specific action to ensure that, as much as possible, a hazard is not created.

**ATLANTA STEEL ERECTORS & WILLIAMS ERECTION COMPANY is responsible for:**

- Substitution of less hazardous products for those that contain crystalline silica is required.
- Ensuring that the materials (e.g., tools, equipment, personal protective equipment) and other resources (i.e., worker training materials) required to fully implement and maintain this exposure control plan (ECP) are readily available where and when they are required.
- Providing a job-specific ECP for each project, which outlines in detail the work methods and practices that will be followed on each site. Considerations will include:
  - Availability and delivery of all required tools/equipment
  - Scope and nature of grinding work to be conducted
  - Control methods to be used and level of respiratory protection required
  - Coordination plan

56

## Estimate Erection Plan cont.

### We price the plan:

#### Labor:

- Raising gang(s)
- Plumbing and perimeter safety gang
- Bolt up
- Welding
- Decking
- Stud crew
- Stair crew
- Miscellaneous crew
- Site support
- Travel and per diem
- Weather delay estimate

#### Equipment:

- Cranes
- Man lifts
- Welding equipment
- Generator (if no power)
- Air compressor
- Hoisting



57

## Pricing continued:

#### Tools and supplies:

- Welding electrode
- Preheating supplies
- Rigging
- Safety cable
- Posts
- Personal protection equipment
- Fuel
- Small tools
- Delivery

#### Formalize the:

### Erection Scope, Assumptions and Exclusions



58

## Erection Scope and Provisions

- Engineered lift plan and logistics plan is not required or included.
- Price Based on all wide flange bracing with bolted splices.
- Welded Column Splices to be converted to PJP to resist indicated loads and an erection load of 200 Kip Feet of Moment.

#### PROVISIONS:

- Access inside and around structure, including all roads, ramps, etc. to be provided and maintained by the general contractor.
- All steel and deck shall be sequenced by Williams Erection Company, delivered to the hook by the fabricator.
- No Marshaling of steel is included in this proposal. Controlling contractor (GC) to provide adequate area for unloading and shakeout of material within reach of the erecting cranes.
- Fabricator to provide a 13/16" diameter hole approximately 1' from each end of the top flange of each beam or girder framing column to column only for safety tie off system. Sketch available upon request.



59

## PROVISIONS CONT'D.

- Horizontal and vertical control lines to be by the general contractor.
- We include two strands of 3/8" galvanized aircraft cable to be installed at the perimeter and all major interior openings (including roof). Maintenance and removal will be by the general contractor including all handrail posts and becomes the property of the general contractor.
- This proposal is based on the current edition of AISC "Code of Standard Practice".
- Power will be provided by the general contractor. 480 Volts, 3-Phase, 600 Amps. Including cost of power, hook up and material.
- All bent plate or continuous angles shall be shipped loose. If plate is loose then shop attach studs or deform anchors to vertical leg. Fabricator to provide outriggers for all bent plate 1'-0" or greater.



60



**PROVISIONS CONT'D.**

- Fabricator to shop assemble all support frames to maximum extent possible.
- Sidelaps of all floor deck shall be "Button Punched".

**Exclusions:**

- Cost of bond
- Waiver of subrogation
- Builders Risk Deductible
- Liquidated Damages in excess of 1% of contract price



61

**Pricing wrap up:**

- Total cost (this is truly direct cost)
- Mark up
- Base sales price
  
- Requested alternates



62

**Bid Types:**


- Steel in Place – Fabrication and Erection
- Sealed Bid Erection Only
- Cost plus not to exceed
- Commitment from Fabricator
- Auction



63

**Steel Erection Contractual Relationships**

- Subcontracted to the Structural Fabricator



64



### Steel Erection Scary Contractual Requirements

- **Contract flow down - Incorporation of all the contracts above**
- **Schedule changes**
- Subcontractor agrees to comply with any schedule for the Project set forth in the Contract Documents, **and with any subsequent updates or modifications to the Project schedule issued by the Owner, the Prime Contractor, or Fabricator.**
- **Pay if Paid**  
Progress Payments, less applicable retainage, shall be paid to Subcontractor within 7 days after Fabricator receives payment from the Prime Contractor. To the extent enforceable under applicable law, **Fabricator's receipt of payment from the Prime Contractor is specifically made a condition precedent to Fabricator's obligation to make payment to the Subcontractor.** In the event of such nonpayment by the Owner or Prime Contractor, Subcontractor's rights and remedies shall be the same as those available to Fabricator under the Trade Contract.



65

- **Requirement to proceed without change orders**

Time of the Essence - The Subcontractor agrees and recognizes that time is of the essence in its performance of this Subcontract Agreement. Subcontractor further recognizes that the Owner, the Prime Contractor, and Fabricator may sustain financial loss if the Project or any part of it is delayed because the Subcontractor fails to perform any or all of its Work in accordance with the Contract Subcontract Agreement. Subcontractor agrees to begin performance when directed by Fabricator and to perform in such a manner, at such times, and in such order as Fabricator may direct, so as not to delay the Project. **Subcontractor agrees that in the event of any claim, dispute or other matter in question arising out of or relating to this Subcontract Agreement (hereinafter "dispute"), the Subcontractor shall continue to diligently perform all obligations as required under this Agreement and will not directly or indirectly stop or delay the Work in any way, notwithstanding the existence of such dispute(s).**



66

With the signing of the contract the marriage is official.  
Torchio's two laws of construction contracts:

1. **A bad contract with a good customer is much to be preferred to a good contract with a bad customer**
2. **Perfect performance of the parties obviates the contract.**

**The way to assure the contract stays in the drawer is to perform as expected and communicate with your customer.**

The Golden Rule  
Bonding  
Legal Process  
Mediation  
Arbitration  
Court



67

## **PART TWO** **We have a job!**

The marriage occurs for the particular job.

- Contract finalization
- Pre detailing meeting
- Requested changes for ease of erection or economic betterment





68





**Tower Steel Erection**

Sequence #	Sequence Location	Description – 300 Tryon Tower Erection
11, 21, 31,41,51	Ground Floor / Main	Receive Sequence Steel, unload, crib and spread in laydown area or erect off truck
11, 21, 31,41,51	Ground Floor / Main	Stand columns, level and plumb
11, 21, 31,41,51	Ground Floor / Main	Erect sequence beams, boxing in columns – install at least 2 bolts per connection
11,21,31,41,51	Ground Floor / Main	Weld Connections and Column Splices as per drawings
11, 21, 31,41,51	Ground Floor / Main	Connect Sequence Steel to Embeds and Connections at Core
11, 21, 31,41,51	Ground Floor / Main	Install plumb cables in accordance with stabilization plan
11,21,31,41,51	Ground Floor / Main	Final Bolt, Up, Weld, Detail & Deck Sequences & Perimeter Cable
61,71,81	Ground Floor / Core	Receive Sequence Steel, unload, crib and spread in laydown area or erect off truck
61,71,81	Ground Floor / Core	Stand columns, level and plumb
61,71,81	Ground Floor / Core	Erect sequence beams, boxing in columns – install at least 2 bolts per connection
61,71,81	Ground Floor / Core	Connect Sequence Steel to Embeds and Connections At Core
61,71,81	Ground Floor / Core	Weld Connections and Column Splices as per drawings
61,71,81	Ground Floor / Core	Install plumb cables in accordance with stabilization plan
61,71,81	Ground Floor / Main	Final Bolt, Up, Weld, Detail & Deck Sequences & Perimeter Cable
61,71,81	Ground Floor / Main	Inspect, Turn Over Floor / Obtain Floor Turnover Documentation
Transfer Truss	Ground Floor / Main	Receive and Set Up Leihberr 1220 5.2 Crane & Inspect
Transfer Truss	Ground Floor / Main	Inspect & Layout Special Truss Erection Rigging
Transfer Truss	Ground Floor / Main	Assemble Transfer Truss in Laydown Area
Transfer Truss	Ground Floor / Main	Confirm Inspection and Operator's license for TC-1 21 LC 400
Transfer Truss	Ground Floor / Main	Follow Critical Lift Plan for Transfer Truss
Transfer Truss	Ground Floor / Main	Bolt / Weld Truss Connections per Truss Connection Detail
12,22,32,42,52	1M / Main	Receive Sequence 5 Steel, unload, crib and spread in laydown area
12,22,32,42,52	1M / Main	Erect sequence beams, boxing in columns – install at least 2 bolts per connection
12,22,32,42,52	1M / Main	Weld Connections and Column Splices as per drawings
12,22,32,42,52	1M / Main	Connect Sequence Steel to Embeds and Connections at Core
12,22,32,42,52	1M / Main	Install plumb cables in accordance with stabilization plan
12,22,32,42,52	1M / Main	Final Bolt, Up, Weld, Detail & Deck Sequences & Perimeter Cable
62,72,82	1M / Core	Receive Sequence Steel, unload, crib and spread in laydown area or erect off truck
62,72,82	1M / Core	Erect sequence beams, boxing in columns – install at least 2 bolts per connection




**Complete Joint Penetration (CJP) for W14 x 1194**

Assume 30 degree bevel, 3/8 root - AWS D1.1 Prequalified B U 4a (leaving out the web)

Flange weld area  $6'' \times 3.46'' \times 24'' = 498 \text{ in}^3$   
 Root opening  $2 @ 6'' \times .375 \times 24'' = 108 \text{ in}^3$   
 Run off tabs  $4 @ (6'' \times 3.46 \times 2'')/2 = 83 \text{ in}^3$

**Total Volume 690 in<sup>3</sup> Steel weight 193 lbs.  
 FCAW weight 230 lbs.**

Assuming a welder deposits 35 lbs. of FCAW an 8 hour shift this is a **6.5 Man day column splice**



77



78



79


**AWS D1.1 Currently**  
**AWS D1.1 D 2020**

CL	Level	upper col	lower col	Tension	<b>S</b> D	<b>E</b> S
F5	4	W14x1194	W14x1400	4295	3.25	3.125
F5	6	W14x1194	W14x1194	3570	2.75	2.625
F5	8	W14x1194	W14x1194	2885	2.375	2.25
F5	10	W14x873	W14x1194	2236	2.375	2.25
F5	12	W14x808	W14x873	1646	1.875	1.75
F5	15	W14x605	W14x808	1110	1.625	1.5
F5	17	W14x257	W14x605	675	1.25	1.125
F5	19	W14x257	W14x257	285	0.875	0.75
F5	21	W14x257	W14x257	105	0.75	0.625
F5	23	W14x257	W14x257	165	0.875	0.75
F5	25	W14x257	W14x257	220	0.875	0.75
F5	27	W14x90	W14x257	55	NA	CJP
G4	4	W14x1194	W14x1400	1510	1.5	1.375
G4	6	W14x1194	W14x1194	1165	1.25	1.125
G4	8	W14x1194	W14x1194	860	1.125	1
G4	10	W14x873	W14x1194	590	1.125	1
G4	12	W14x808	W14x873	355	0.875	0.75
G4	15	W14x605	W14x808	170	0.75	0.625
G4	17	W14x257	W14x605	21	0.625	0.5
G4	19	W14x257	W14x257	0	0.625	0.5
G4	21	W14x257	W14x257	155	0.75	0.625
G4	23	W14x257	W14x257	355	1	0.875
G4	25	W14x257	W14x257	530	1.125	1
G4	27	W14x90	W14x257	85	NA	CJP
G5	4	W14x1194	W14x1400	3575	2.75	2.625
G5	6	W14x1194	W14x1194	2885	2.375	2.25
G5	8	W14x1194	W14x1194	2285	2	1.875

PJP Welds sized per tension and moment loads  
and use of 70 KSI Filler Metal



80





**PJP for W14 x 1194**

Assume 45 degree bevel, AWS D1.1 Prequalified BTC P4 GF Weld Groove from Table 3.25"  
 Flange weld area  $3.25'' \times 3.25'' \times 24'' = 254 \text{ in}^3$   
 Root opening 0  
 Run off tabs  $4 @ (3.25'' \times 3.25 \times 1.5'')/2 = 32 \text{ in}^3$   
 Total Volume  $286 \text{ in}^3$  Steel weight 80 lbs. FCAW weight 95 lbs.

Assuming a welder deposits 50 lbs. of FCAW an 8 hour shift this is a 1.9 Man day column splice

Labor saving by using PJP = 4.6 man days  
 Direct labor cost at \$50 per hour = \$1,840  
 Indirect savings ??



## Some Interesting Jobs and Special Erection Considerations



85



86






87










100 ton Hillman Roller  
2 per Truss





Lifting Assembly  
(no welds) <sup>88</sup>













Alternative to use of large cranes:

Derrick VS  
500 ton  
Truck Crane


\$3,500/  
Month

VS

\$4,000/ day



105




PHIPPS PLAZA STIFFERES DERRICK SETUP PLAN

NOTE: SEE DIMENSIONS, SET 1 AND SET 2 SHALL BE COMBINED TO OBTAIN TOTAL AND CORRECT CENTER FOR NUMBER OF STIFFERES REQUIRED.

REV	DESCRIPTION	DATE	BY	CHK
1	ISSUED FOR CONSTRUCTION	11/15/18	...	...



106



RETRACTED LOAD & RADIUS CHART REF. EP-2

FOR CLARITY VIEW DRAWING EP-4.1



107




Williams Erection Company

Phipps Plaza Setup # 1 Between 8 & 12 Lines

Weight	Radius - Feet	Degree From Center	Starting Point
			14'-0" Radius
350	34'-9"	-60.24	-43.76
820	43'-9"	-52.04	-43.76
300	48'-0"	-40.5	-43.76
650	38'-10"	-46.13	-43.76
650	32'-9"	-34.74	-43.76
800	39'-2"	-20.94	-43.76
650	28'-5"	-19.12	-43.76
1850	22'-2"	-89.06	-43.76
650	26'-11"	0	-43.76
300	36'-8"	5.08	-43.76
855	28'-0"	13.39	-43.76
680	33'-8"	24.56	-43.76
370	48'-8"	25.56	-43.76
500	37'-5"	29.59	-43.76
920	40'-2"	35.8	-43.76
1150	41'-9"	42.11	-43.76
370	29'-7"	44.18	-43.76
730	60'-9"	43.72	-43.76
500	46'-9"	45.87	-43.76
500	50'-11"	50.24	-43.76
500	55'-4"	53.94	-43.76
1750	47'-0"	63.16	-43.76
1150	63'-9"	61.32	-43.76



108



## Engineered Erection Plans


Big and Light

Big and Heavy




113

Georgia Tech Football  
Practice Facility  
Engineered Erection  
Stability Plan  
Structure Not Self  
Supporting Until  
complete



114



GENERAL ERECTION NOTES:	MATERIALS AND CONNECTIONS:
1. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	1. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
2. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	2. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
3. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	3. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
4. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	4. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
5. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	5. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
6. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	6. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
7. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	7. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
8. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	8. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
9. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.	9. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.

REMOVAL OF TEMPORARY ERECTION AIDS:
1. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
2. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
3. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
4. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
5. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
6. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
7. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
8. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.
9. ALL DIMENSIONS ARE UNLESS OTHERWISE SPECIFIED.

GEORGIA TECH FOOTBALL PRACTICE FACILITY ENGINEERED ERECTION STABILITY PLAN
DATE: 11/15/17
SCALE: 1/8\"
PROJECT: GEORGIA TECH FOOTBALL PRACTICE FACILITY
ARCHITECT: HOK
ENGINEER: AISC
114



116

**GENERAL ERECTION NOTES:**

1. THIS DOCUMENT PROVIDES AN ENGINEERED SEQUENCE FOR ERECTION THAT MUST BE FOLLOWED AS DESCRIBED HEREIN UNLESS REVISIONS ARE APPROVED IN WRITING BY THE ERECTION ENGINEER (SDI).
2. THE ERECTION OF MISCELLANEOUS FRAMING, THE USE OF SUPPLEMENTARY CABLES FOR PLUMBING OF COLUMNS, AND THE METHODS AND SEQUENCING OF ALL OTHER MISCELLANEOUS ERECTION-RELATED ACTIVITIES NOT SPECIFICALLY COVERED BY THIS DOCUMENT SHALL BE PERFORMED UNDER THE DIRECTION OF THE ERECTOR.
3. AN ERECTION PERIOD OF 6 WEEKS HAS BEEN ASSUMED IN THE CALCULATION OF CONSTRUCTION WIND LOADING.
4. ERECTOR HAS THE SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.
5. BRACING OF THE COLUMNS AT GRID LINE J HAS BEEN DESIGNED FOR WIND LOADS UP TO 25MPH. IF WINDS EXCEED THIS LIMIT, IT IS EXPECTED THAT THE BRACES WILL FAIL, AND THAT LARGE DEFLECTIONS OF THE STRUCTURE COULD OCCUR - THOUGH COLLAPSE WILL BE PREVENTED BY THE CABLE DIAPHRAGM. IF WINDS EXCEED 25MPH AT ANY TIME DURING THE CONSTRUCTION PERIOD, BRACES, CABLES, AND ALL CONNECTIONS SHALL BE INSPECTED PRIOR TO PROCEEDING WITH ERECTION.
6. IF WINDS EXCEEDING 25MPH ARE ANTICIPATED, THE BRACING INDICATED IN THESE DOCUMENTS MUST BE IN PLACE AND PROPERLY SECURED PRIOR TO LEAVING THE JOBSITE.

**REMOVAL OF TEMPORARY ERECTION AIDS**

1. BRACES TO COLUMNS AT GRID LINE "J" TO REMAIN UNTIL COMPLETION OF BUILDING ENVELOPE.
2. TEMPORARY CABLE BRACED FRAMES AT GRID LINES "1" & "9" TO REMAIN UNTIL COMPLETION OF BUILDING ENVELOPE.
3. DIAPHRAGM CABLE BRACING BETWEEN GRID LINES "1" & "2" AND "8" & "9" SHALL REMAIN IN PLACE UNTIL COMPLETION OF BUILDING ENVELOPE.

DIAPHRAGM CABLE BRACING BETWEEN GRID LINES "2" & "8" MAY BE REMOVED AFTER A MINIMUM OF 7 FOLLOWING DAYS HAVE BEEN COMPLETELY DECKED (E.G. CABLES BETWEEN "1" & "2" & "8" & "9" MAY BE REMOVED AFTER DECK IS COMPLETE THROUGH "1" & "2" & "8" & "9").


4. HSS STRUT BETWEEN GRID LINES "G" AND "H" ADJACENT TO GRID LINE "9" TO REMAIN UNTIL COMPLETION OF BUILDING ENVELOPE.



117

X01.1 ERECT W30 COLUMNS AT GRID LINES J+4 AND J-9.  
X01.2 ERECT PERMANENT HORIZONTAL BRACING BETWEEN COLUMNS.

NOTE: IF WIND SPEED IS ANTICIPATED TO EXCEED 25MPH, COLUMN BRACES SHALL BE IN PLACE IN ACCORDANCE WITH SHEETS X03 AND X04.




SDI SEQUENCE X01

118

X03.1 ERECT TILT-UP BRACES TO W30 COLUMNS AT GRIDS J-3, J-4, J-5, J-6, AND J-7. SEE SHEET X04 FOR DETAILS.  
X03.2 WELD HALF WALKERS TO TOP OF BASE PLATES AT COLUMNS ON GRID LINE J WITH 1/2" TILT-UP BEAMS ALL AROUND.  
X03.3 ERECT W12 ARCH BEAM AT TOP OF W30 COLUMNS.

NOTE: IF WIND SPEED IS ANTICIPATED TO EXCEED 25MPH PRIOR TO SETTING OF TRUSS AT GRID LINE J, COLUMNS AT GRID LINES J+1, J-2, J-8, AND J-9 SHALL BE COVERED TO 2000 R/WIN. (SECTION IN EACH DIRECTION OF TEMPORARILY TACK DOWN).





SDI SEQUENCE X03





119



SDI SEQUENCE X04

120



**Big and Heavy**



Project: RSA Judicial Office Building  
Location: Montgomery, AL  
GC: Bailey Harris  
Fabricator: SteelFab

Project consisted of 3- 150 ft. span two story transfer trusses supporting a nine story building over a National Historic Register Building in downtown Montgomery. The trusses were assembled in place utilizing an outrigger skyhook system anchored to the adjacent concrete structure for the first truss. Truss elevation was managed by hydraulic jacking system.

Engineered erection plan and procedure was provided.

Total Truss Weight for Each Truss – 300 tons fully assembled

Hoisting by 500 ton hydraulic Liebherr Lifting Crane



125



Project: RSA Judicial Office Building  
Location: Montgomery, AL  
GC: Bailey Harris  
Fabricator: SteelFab

Erection and assembly of the final truss sections supported by the skyhook system connected to previously erected trusses. Each truss consisted of over 400 ft. of field welding and 16,000 bolts per truss.



126


## ERECTION NOTES

**GENERAL ERECTION NOTES**

1. THIS DOCUMENT PROVIDES AN ENGINEERED SEQUENCE FOR ERECTION THAT MUST BE FOLLOWED AS DESCRIBED HEREIN UNLESS REVISIONS ARE APPROVED IN WRITING BY STANLEY D. LINDSEY AND ASSOCIATES (SDL).
2. THE ERECTION OF MISCELLANEOUS FRAMING, THE USE OF SUPPLEMENTARY CABLES FOR PLUMBING OF COLUMNS, AND THE METHODS AND SEQUENCING OF ALL OTHER MISCELLANEOUS ERECTION-RELATED ACTIVITIES NOT SPECIFICALLY COVERED BY THIS DOCUMENT SHALL BE PERFORMED UNDER THE DIRECTION OF THE ERECTOR.
3. AN ERECTION PERIOD OF SIX WEEKS TO ONE YEAR HAS BEEN ASSUMED FOR THE PODIUM STEEL IN THE CALCULATION OF CONSTRUCTION WIND LOADINGS.
4. ERECTOR HAS THE SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.
5. CONNECTION DESIGN OF TRUSS CONNECTIONS FOR CONSTRUCTION LOADS WAS DELEGATED TO STEELFAB INC. FINAL CONSTRUCTION FORCES WERE PROVIDED TO STEELFAB BY SDL ON JUNE 20, 2011, WITH A SUPPLEMENTARY EMAIL DATED JULY 29, 2011.
6. THE ANALYSIS AND DESIGN OF TEMPORARY BRACED FRAMES AND THEIR CONNECTIONS FOR ERECTION WAS PERFORMED BY SDL AS ILLUSTRATED IN THE X4 SERIES DRAWINGS DATED JUNE 20, 2011.
7. THE GENERAL ERECTION SEQUENCING INFORMATION PROVIDED IN THIS DOCUMENT SHALL BE USED IN CONJUNCTION WITH THE DETAILED ERECTION DRAWINGS PROVIDED BY STEELFAB INC.
8. MEMBERS ILLUSTRATED WITHIN EACH SEQUENCE IN RED ARE NEW TO THAT SEQUENCE, AND MEMBERS ILLUSTRATED IN BLUE HAVE BEEN PREVIOUSLY ERECTED.
9. THE EXACT ORDER OF THE SUB#STEPS (LETTERED A, B, C, ETC) WITHIN EACH MAIN TRUSS ERECTION STEP IS NOT CRITICAL PROVIDED THAT ALL STEPS ARE COMPLETE PRIOR TO RELEASING THE TRUSS SECTION FROM THE CRANE.
10. ALL COLUMN BASEPLATES MUST BE GROUTED AND GROUT MUST ACHIEVE 75% OF ITS SPECIFIED 28#DAY COMPRESSIVE STRENGTH PRIOR TO ERECTION OF THE SUPPORTED TRUSS SECTION.
11. SEE STEELFAB SHEET E250 FOR TYPICAL TRUSS DETAILS INCLUDING ERECTION SEQUENCING INFORMATION FOR THE COMPLETION OF TRUSS CHORD SPLICES, WING PLATE CONNECTIONS, LOOSE COVER PLATES, AND TEMPORARY GUSSET ERECTION AIDS.

**MATERIALS AND CONNECTIONS**

1. SHOWN CONNECTIONS UNLESS OTHERWISE NOTED SHALL CONFORM TO AISC 360, 350 AND 305.
2. UNLESS OTHERWISE SPECIFIED, ALL STEEL SHALL BE A36.
3. WELDS SHALL BE MADE BY A QUALIFIED WELDER.
4. SINGLE GUSSETS SHALL BE AS NOTED ON PLAN AND CONSTRUCTED AS FOLLOWS:
  - 1) 1/4" ELEVATOR: 1/4" CABLE STEEL X 1/4" THK WDR. BRACED END PORT
  - 2) 1/4" ELEVATOR: 1/4" CABLE STEEL X 1/4" THK WDR. BRACED END PORT
  - 3) 1/4" ELEVATOR: 1/4" CABLE STEEL X 1/4" THK WDR. BRACED END PORT
5. WELDS SHALL BE MADE TO MATCH DETAILS, THE WELDING NUMBER OF 10000 SHALL BE USED.
6. ERECTOR SHALL VERIFY THE EXACT ORDER OF THE SUB#STEPS (LETTERED A, B, C, ETC) WITHIN EACH MAIN TRUSS ERECTION STEP IS NOT CRITICAL PROVIDED THAT ALL STEPS ARE COMPLETE PRIOR TO RELEASING THE TRUSS SECTION FROM THE CRANE.



3D OVERALL PODIUM VIEW



ERECTION NOTES  
STEELFAB  
08/05/11  
X5-1




127

**Erection Stability Plan for Heavy Structure with Life Safety Issues**


1. THIS DOCUMENT PROVIDES AN ENGINEERED SEQUENCE FOR ERECTION THAT MUST BE FOLLOWED AS DESCRIBED HEREIN UNLESS REVISIONS ARE APPROVED IN WRITING BY STANLEY D. LINDSEY AND ASSOCIATES (SDL).
2. THE ERECTION OF MISCELLANEOUS FRAMING, THE USE OF SUPPLEMENTARY CABLES FOR PLUMBING OF COLUMNS, AND THE METHODS AND SEQUENCING OF ALL OTHER MISCELLANEOUS ERECTION-RELATED ACTIVITIES NOT SPECIFICALLY COVERED BY THIS DOCUMENT SHALL BE PERFORMED UNDER THE DIRECTION OF THE ERECTOR.
3. AN ERECTION PERIOD OF SIX WEEKS TO ONE YEAR HAS BEEN ASSUMED FOR THE PODIUM STEEL IN THE CALCULATION OF CONSTRUCTION WIND LOADINGS.
4. ERECTOR HAS THE SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.
5. CONNECTION DESIGN OF TRUSS CONNECTIONS FOR CONSTRUCTION LOADING WAS DELEGATED TO STEELFAB INC. FINAL CONSTRUCTION FORCES WERE PROVIDED TO STEELFAB BY SDL ON JUNE 20, 2011, WITH A SUPPLEMENTARY EMAIL DATED JULY 29, 2011.
6. THE ANALYSIS AND DESIGN OF TEMPORARY BRACED FRAMES AND THEIR CONNECTIONS FOR ERECTION WAS PERFORMED BY SDL AS ILLUSTRATED IN THE X4 SERIES DRAWINGS DATED JUNE 20, 2011.
7. THE GENERAL ERECTION SEQUENCING INFORMATION PROVIDED IN THIS DOCUMENT SHALL BE USED IN CONJUNCTION WITH THE DETAILED ERECTION DRAWINGS PROVIDED BY STEELFAB INC.
8. MEMBERS ILLUSTRATED WITHIN EACH SEQUENCE IN RED ARE NEW TO THAT SEQUENCE, AND MEMBERS ILLUSTRATED IN BLUE HAVE BEEN PREVIOUSLY ERECTED.
9. THE EXACT ORDER OF THE SUB#STEPS (LETTERED A, B, C, ETC) WITHIN EACH MAIN TRUSS ERECTION STEP IS NOT CRITICAL PROVIDED THAT ALL STEPS ARE COMPLETE PRIOR TO RELEASING THE TRUSS SECTION FROM THE CRANE.
10. ALL COLUMN BASEPLATES MUST BE GROUTED AND GROUT MUST ACHIEVE 75% OF ITS SPECIFIED 28#DAY COMPRESSIVE STRENGTH PRIOR TO ERECTION OF THE SUPPORTED TRUSS SECTION.
11. SEE STEELFAB SHEET E250 FOR TYPICAL TRUSS DETAILS INCLUDING ERECTION SEQUENCING INFORMATION FOR THE COMPLETION OF TRUSS CHORD SPLICES, WING PLATE CONNECTIONS, LOOSE COVER PLATES, AND TEMPORARY GUSSET ERECTION AIDS.



128



129




130

Grid	Piece wt.	Weighed	Rigging	Lift Wt.	Total	Radius
8-D-C	62,825	X	4500	67,325	67,325	53'-11"
2-D-F	186,976	X	6000	192,976	398,174	48'-5"
2-C-D	199,198	X	6000	205,198		44'-3"
3-D-F	160,728	X	6000	166,728	330,870	53'-8"
3-C-D	158,142	X	6000	164,142		48'-9"
E-2-3	24,515	X	4500	29,015	29,015	56'-3"
D-2-3	47,968	X	4500	52,468	52,468	69'-3"
F-2-3	56,584	X	4500	61,084	61,084	37'-2"
C-2-3	58,158	X	4500	62,658	62,658	20'-0"
D-3-5	109,930	X	4500	108,430	108,430	70'-7"
E-3-6	90,926	X	4500	95,426	95,426	88'-7"


Grid Piece wt. Weighed Rigging Lift Wt. Total Radius

131




ERECTION SEQUENCE STEPS

- X5-2-1: ERECT TEMPORARY BRACED FRAME EBF-1 AND ASSOCIATED COLUMNS ALONG GRID LINE F BETWEEN GRID LINES 6 AND 7 (SEE X4 AND E800 SERIES SHEETS)
- X5-2-2: ERECT TEMPORARY BRACED FRAME EBF-2 AND ASSOCIATED COLUMNS ALONG GRID LINE F BETWEEN GRID LINES 2 AND 3 (SEE X4 AND E800 SERIES SHEETS)
- X5-2-3: ERECT COLUMNS F-4 AND F-5
- X5-2-4: ONCE PLAN LOCATIONS OF COLUMNS HAVE BEEN VERIFIED: PLUMB COLUMNS, GROUT BASEPLATES, AND BRACE/FILL AS REQUIRED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND GEOTECHNICAL RECOMMENDATIONS




132







133



134




135




136







137



138



139



140





## Individual Webinar Registrants

### CEU/PDH Certificates

Within 2 business days...

- You will receive an email on how to report attendance from: [registration@aisc.org](mailto:registration@aisc.org).
- Be on the lookout: Check your spam filter! Check your junk folder!
- Completely fill out online form. Don't forget to check the boxes next to each attendee's name!



## Individual Webinar Registrants

### CEU/PDH Certificates

Within 2 business days...

- New reporting site (URL will be provided in the forthcoming email).
- Username: Same as AISC website username.
- Password: Same as AISC website password.



## 8-Session Registrants

### CEU/PDH Certificates

One certificate will be issued at the conclusion of all 8 sessions.



## 8-Session Registrants

Access to the quiz: Information for accessing the quiz will be emailed to you by Wednesday. It will contain a link to access the quiz. EMAIL COMES FROM [NIGHTSCHOOL@AISC.ORG](mailto:NIGHTSCHOOL@AISC.ORG)

Quiz and Attendance records: Posted Tuesday mornings.  
[www.aisc.org/nightschool](http://www.aisc.org/nightschool) - click on Current Course Details.

Reasons for quiz:

- EEU – must take all quizzes and final to receive EEU
- CEUs/PDHS – If you watch a recorded session you must take quiz for CEUs/PDHS.
- REINFORCEMENT – Reinforce what you learned tonight. Get more out of the course.

NOTE: If you attend the live presentation, you do not have to take the quizzes to receive CEUs/PDHS.



## 8-Session Registrants

**Access to the recording:** Information for accessing the recording will be emailed to you by this Wednesday. The recording will be available for three weeks. For 8-session registrants only. EMAIL COMES FROM NIGHTSCHOOL@AISC.ORG.

**CEUs/PDHS** – If you watch a recorded session you must take AND PASS the quiz for CEUs/PDHS.



## Night School Resources for 8-session package Registrants

Find all your handouts, quizzes and quiz scores, recording access, and attendance information all in one place!



## Night School Resources for 8-session package Registrants

Go to [www.aisc.org](http://www.aisc.org) and sign in.



### Login

If you're an existing customer, please enter your username and password.

#### USERNAME

Enter your username

#### PASSWORD

Enter your password

Remember Me


#### DON'T HAVE AN ACCOUNT?

My AISC allows you to access Engineering Journal articles and Design Guides you have downloaded from the bookstore.

[REGISTER NOW](#)

## Night School Resources for 8-session package Registrants

Go to [www.aisc.org](http://www.aisc.org) and sign in.



## Night School Resources for 8-session package Registrants



### Night School 13: Design of Industrial Buildings

#### 8-SESSION PACKAGE RESOURCES

Event	Date	Handouts	Video	Quiz	Attendance
NS13 - Design Criteria	1/30/2017 7:00:00 PM	<a href="#">Handouts</a>	<a href="#">Video</a>	Pass Score 80	Pending
NS13 - Economic Considerations	2/6/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 02/06/2017 5pm EST	Available 02/06/2017 5pm EST	Pending
NS13 - Lateral Load Systems and Details	2/13/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 02/13/2017 5pm EST	Available 02/13/2017 5pm EST	Pending
NS13 - Preliminary Design Procedures	2/27/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 03/02/2017 5pm EST	Available 03/02/2017 5pm EST	Pending
NS13 - Crane Grid Design and Frame Analysis	3/6/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 03/06/2017 5pm EST	Available 03/06/2017 5pm EST	Pending
NS13 - Frame Member and Connection Design	3/13/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 03/13/2017 5pm EST	Available 03/13/2017 5pm EST	Pending
NS13 - Transfer Crane Grid & Longitudinal Bolt Bracing Design	3/27/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 03/28/2017 5pm EST	Available 03/28/2017 5pm EST	Pending
NS13 - Building Envelope and Bracing Design	4/3/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 04/03/2017 5pm EST	Available 04/03/2017 5pm EST	Pending
NS13 - Final Exam	4/10/2017 7:00:00 PM	<a href="#">Handouts</a>	Available 04/10/2017 5pm EST	Available 04/10/2017 5pm EST	Pending

## Night School Resources for 8-session package Registrants

- Weekly “quiz and recording” email.
- Weekly updates of the master Quiz and Attendance record found at [www.aisc.org/nightschool](http://www.aisc.org/nightschool). Scroll down to Quiz and Attendance records.
  - Updated on Tuesday mornings.



## Night School Resources for 8-session package Registrants

- Webinar connection information:
  - Found in your registration confirmation/receipt.
  - Reminder email sent out Monday mornings.
- Link to handouts also found here.



AISC | Thank you

